

**Regional Recreation Corporation of Wood Buffalo (“RRC”)
Fort McMurray, Alberta
Request for Proposal (“RFP”)
For
Supply and Install Cooling Tower**

RFP #2018-03-08-Supply-and -Install-Cooling-Tower

ADDENDUM 1

Responses from the Regional Recreation Corporation of Wood Buffalo (in red font) to the following questions received in relation to the aforementioned Request for Proposal are reflected in this Addendum.

1. After reviewing the attached document, we couldn't find the duty or size of the existing tower, or the new one. Furthermore, we need the details on the scope of works, i.e. material specification, quantities, etc.? **The present cooling tower is sized to accommodate a 400 tons refrigeration plant. What we are looking for is a contractor to supply and install a condenser that will accommodate the capacity of a refrigeration plant that uses four screw compressors that generate 400 tons of refrigeration. Given that our facility is in Northern Alberta (50th parallel) we have issues with conventional evaporative condensers or cooling towers. We are asking that air cooled condensers or low water systems be put forward in the RFP.**